ISSUE: Certificate of Appropriateness for alterations (small cell facility)

APPLICANT: AT&T Mobility

LOCATION: Old and Historic Alexandria District

Dominion Energy utility pole near 432 South Columbus Street


ZONE: CL/Commercial Low Zone

STAFF RECOMMENDATION

Staff recommends approval of the Certificate of Appropriateness, as submitted.

GENERAL NOTES TO THE APPLICANT

- 1. APPEAL OF DECISION: In accordance with the Zoning Ordinance, if the Board of Architectural Review denies or approves an application in whole or in part, the applicant or opponent may appeal the Board's decision to City Council on or before 14 days after the decision of the Board.
- 2. COMPLIANCE WITH BAR POLICIES: All materials must comply with the BAR's adopted policies unless otherwise specifically approved.
- 3. BUILDING PERMITS: Most projects approved by the Board of Architectural Review require the issuance of one or more construction permits by Department of Code Administration (<u>including signs</u>). The applicant is responsible for obtaining all necessary construction permits after receiving Board of Architectural Review approval. Contact Code Administration, Room 4200, City Hall, 703-746-4200 for further information.
- 4. ISSUANCE OF CERTIFICATES OF APPROPRIATENESS AND PERMITS TO DEMOLISH: Applicants must obtain a copy of the Certificate of Appropriateness or Permit to Demolish PRIOR to applying for a building permit. Contact BAR Staff, Room 2100, City Hall, 703-746-3833, or preservation@alexandriava.gov for further information.
- 5. EXPIRATION OF APPROVALS NOTE: In accordance with Sections 10-106(B), 10-206(B) and 10-307 of the Zoning Ordinance, any Board of Architectural Review approval will expire 12 months from the date of issuance if the work is not commenced and diligently and substantially pursued by the end of that 12-month period.
- 6. HISTORIC PROPERTY TAX CREDITS: Applicants performing extensive, certified rehabilitations of historic properties may separately be eligible for state and/or federal tax credits. Consult with the <u>Virginia Department of Historic Resources (VDHR)</u> prior to initiating any work to determine whether the proposed project may qualify for such credits.



I. <u>APPLICANT'S PROPOSAL</u>

The applicant is requesting a Certificate of Appropriateness to replace the existing concrete street light pole in the right-of-way near the property at 432 South Columbus Street with a taller metal pole on top of which a 5G small cell facility and a 4G antenna will be installed along with the associated equipment which will be mounted to the pole.

Certificate of Appropriateness

- Replace the existing 23'-0" tall concrete street light pole with a new 33'-0" HAPCO aluminum street light pole.
- Install a AT&T 5G small cell antenna facility strap mounted at 25'-0" above grade
- Install a 4G OMNI antenna on top of the pole, the overall antenna height is 6'-5"
- Install a RAYCAP 200 AMP meter box on the pole at 4'-6" from grade
- Remove the existing pole

Site context

The subject concrete pole is located near to the northeast corner of the intersection of South Columbus and Wilkes streets (Figure 1)



Figure 1 - Existing light concrete pole

II. HISTORY

The property at 432 South Columbus Street is a three-story townhouse built in **2016**. There is a six-story multifamily building built in 1976 on the northwest corner, a two-story townhouse on the southwest corner built in 1950, and a two-story townhouse built in 1984 on the southeast corner.

III. ANALYSIS

To address the growing demand for wireless services across the United States, telecommunication providers are increasing the capacity of their networks by deploying small cell antennas within the public right-of-way to reduce the data traffic load on roof-mounted equipment and larger cell towers. Small cell facilities are low-powered antennas that provide wireless service coverage to a limited geographic area (often with ranges of a few hundred feet) and are used to supplement and expand the coverage provided by the traditional, larger-scale network.

In the past three years, Federal and State legislation has been enacted to further streamline the local approval process for cellular facilities, shortening the approval time and limiting jurisdictions' authority. The laws can be contradictory between federal and state in some instances but do recognize that additional guidelines may be necessary in historic districts.

The City has adopted Interim Wireless Facility Aesthetic Guidelines for wireless infrastructure throughout the City which outline specific guidelines related to the replacement of existing utility poles, including:

- pole height may not increase more than 10 feet and may not exceed 50 feet without a special use permit
- replacement poles must be in the same general location as the existing pole
- replacement poles may not cause the removal of an existing tree or cause damaging impacts to trees located in the right-of-way
- wireless facilities must be shrouded, enclosing wires and equipment, and no separate ground mounted equipment is permitted
- wireless facilities must be painted to match the infrastructure

A Certificate of Appropriateness is required in the historic districts under Section 10-103(A) of the Zoning Ordinance, which state that "No building or structure shall be erected, reconstructed, altered or restored within the Old and Historic Alexandria District unless and until an application for a certificate of appropriateness shall have been approved..."

The proposed pole design is the A-8 Metal Light Pole Replacement with 4G and 5G Configuration approved by the City Council in December 2020 (Figure 2).




Figure 2 - Design A-8 approved by the City Council

The overall height of the new pole including the small cell facility is 38'-5". BAR staff has no objection to the taller metal pole or the installation of the small cell facility in this location and finds that painting the equipment the same color as the pole will make them less obvious. The existence of utility poles and overhead wires, street signs, and light poles are part of the urban streetscape, and staff does not believe that the installation of the taller pole with the small cell equipment will adversely impact existing viewsheds.

Therefore, staff recommends approval of the Certificate of Appropriateness as submitted.

STAFF

Marina Novaes, Historic Preservation Planner, Planning & Zoning Tony LaColla, AICP, Land Use Services Division Chief, Planning & Zoning

IV. CITY DEPARTMENT COMMENTS

Legend: C- code requirement R- recommendation S- suggestion F- finding

Zoning

F-1 Height of the pole shall not exceed 50.00 feet without a Special Use Permit. Pole height is 33' feet and overall height is 38' 5"

- F-2 Pole must be in the same general location as existing pole.

 This will be a new pole to replace an existing concrete pole in same location.
- F-3 The pole is not located in a manner that requires the removal of an existing tree or impacts of root zone.

Pole will sit between two young trees.



- F-4 Pole shall be located that meets ADA requirements that do not impede or hinder pedestrian or vehicular travel.
 - **In Compliance**
- F-5 Wireless facility shall be painted to match similar infrastructure on the block or earth tone color. plans indicate facility to be a metal pole

Code Administration

Code Administration has no comments

Transportation and Environmental Services

- R-1 The building permit must be approved and issued prior to the issuance of any permit for demolition, if a separate demolition permit is required. (T&ES)
- R-2 Applicant shall be responsible for repairs to the adjacent city right-of-way if damaged during construction activity. (T&ES)

- R-3 No permanent structure may be constructed over any existing private and/or public utility easements. It is the responsibility of the applicant to identify any and all existing easements on the plan. (T&ES)
- F-1 After review of the information provided, an approved grading plan is not required at this time. Please note that if any changes are made to the plan it is suggested that T&ES be included in the review. (T&ES)
- F-2 If the alley located at the rear of the parcel is to be used at any point of the construction process the following will be required:

 For a Public Alley The applicant shall contact T&ES, Construction Permitting & Inspections at (703) 746-4035 to discuss any permits and accommodation requirements that will be required.

 For a Private Alley The applicant must provide proof, in the form of an affidavit at a minimum, from owner of the alley granting permission of use. (T&ES)
- C-1 The applicant shall comply with the City of Alexandria's Solid Waste Control, Title 5, Chapter 1, which sets forth the requirements for the recycling of materials (Sec. 5-1-99). (T&ES)
- C-2 The applicant shall comply with the City of Alexandria's Noise Control Code, Title 11, Chapter 5, which sets the maximum permissible noise level as measured at the property line. (T&ES)
- C-3 All secondary utilities serving this site shall be placed underground. (Sec. 5-3-3) (T&ES)
- C-4 Any work within the right-of-way requires a separate permit from T&ES. (Sec. 5-2) (T&ES)
- C-5 All improvements to the city right-of-way such as curbing, sidewalk, driveway aprons, etc. must be city standard design. (Sec. 5-2-1) (T&ES)

Alexandria Archaeology

F-1 No archaeological oversight necessary.

V. ATTACHMENTS

- *1 Application Materials*
- 2 Supplemental Materials

ADDRESS OF PROJECT: 432 S Columbus St	
DISTRICT: Old & Historic Alexandria Parker - Gray	□ 100 Year Old Building
TAX MAP AND PARCEL: 074. 04-11-39	zoning: CL
APPLICATION FOR: (Please check all that apply)	
CERTIFICATE OF APPROPRIATENESS	
PERMIT TO MOVE, REMOVE, ENCAPSULATE OR DEMO (Required if more than 25 square feet of a structure is to be demolished/im	
WAIVER OF VISION CLEARANCE REQUIREMENT and/or CLEARANCE AREA (Section 7-802, Alexandria 1992 Zoning Ordina	
WAIVER OF ROOFTOP HVAC SCREENING REQUIREME (Section 6-403(B)(3), Alexandria 1992 Zoning Ordinance)	NT
Applicant: Property Owner Business (Please provide	business name & contact person)
Name: _AT&T Mobility	
Address: 7150 Standard Drive	
City: Hanover State: VA Zip: 2	1076
Phone: E-mail :	
Authorized Agent (if applicable): Attorney Archite	
Name: Smartlink	Phone: <u>301-509-5518</u>
E-mail: brian.taylor@smartlinkgroup.com	
Legal Property Owner:	
Dominion Energy	
3072 Centreville Poad	
Aduless	
City: Herndon State: VA Zip: 2	
Phone: E-mail: austin.d.gore	e@dominionenergy.com
Yes No Is there an historic preservation easement on this Yes No If yes, has the easement holder agreed to the property Yes No Is there a homeowner's association for this property Yes No If yes, has the homeowner's association approved	oposed alterations? erty?

If you answered yes to any of the above, please attach a copy of the letter approving the project.

	BAR Case #
NATURE OF PROPOSED WORK: Please check all that apply	
doors windows sidin	C equipment
DESCRIPTION OF PROPOSED WORK: Please describe the be attached). Description of Work Replacing an existing concrete street light pole for the purposes of installing a Dominion owned metal (HAPCO) street light pole.	
Antennas We will be installing both 4G and 5G antennas to the replacement pole.	
Existing pole height and material. All 3 of the existing poles are concrete. ALEXA_14 (4501 Ford Ave) has an existing height of 30'-and ALEXA_045 (432 South Columbus St) has an existing	
SUBMITTAL REQUIREMENTS:	
Items listed below comprise the minimum supporting materia request additional information during application review. Please Design Guidelines for further information on appropriate treatments	refer to the relevant section of the
Applicants must use the checklist below to ensure the application material that are necessary to thoroughly describe the project. It docketing of the application for review. Pre-application meetings All applicants are encouraged to meet with staff prior to submiss	ncomplete applications will delay the sare required for all proposed additions.
Electronic copies of submission materials should be submitted v	whenever possible.
Demolition/Encapsulation: All applicants requesting 25 squar must complete this section. Check N/A if an item in this section does not be a section of the	
N/A Survey plat showing the extent of the proposed demolition Existing elevation drawings clearly showing all elements Clear and labeled photographs of all elevations of the b	s proposed for demolition/encapsulation.

Description of the alternatives to demolition/encapsulation and why such alternatives are not

to be demolished.

considered feasible.

☐ Description of the reason for demolition/encapsulation.

	BAR Case #
Additions & New Construction: Drawings must be to scale ar	nd should not exceed 11" x 17" unless
approved by staff. All plans must be folded and collated into 3 complete	e 8 1/2" x 11" sets. Additional copies may be

		ed by staff for large-scale development projects or projects fronting Washington Street. Check N/A if an item ection does not apply to your project.
	N/A	Scaled survey plat showing dimensions of lot and location of existing building and other structures on the lot, location of proposed structure or addition, dimensions of existing structure(s), proposed addition or new construction, and all exterior, ground and roof mounted
		equipment. FAR & Open Space calculation form. Clear and labeled photographs of the site, surrounding properties and existing structures, if applicable.
		Existing elevations must be scaled and include dimensions. Proposed elevations must be scaled and include dimensions. Include the relationship to adjacent structures in plan and elevations.
		Materials and colors to be used must be specified and delineated on the drawings. Actual samples may be provided or required.
		Manufacturer's specifications for materials to include, but not limited to: roofing, siding, windows, doors, lighting, fencing, HVAC equipment and walls.
		For development site plan projects, a model showing mass relationships to adjacent properties and structures.
illur	ninate	& Awnings: One sign per building under one square foot does not require BAR approval unless ed. All other signs including window signs require BAR approval. Check N/A if an item in this section does to your project.
		Linear feet of building: Front:Secondary front (if corner lot): Square feet of existing signs to remain: Photograph of building showing existing conditions. Dimensioned drawings of proposed sign identifying materials, color, lettering style and text. Location of sign (show exact location on building including the height above sidewalk). Means of attachment (drawing or manufacturer's cut sheet of bracket if applicable). Description of lighting (if applicable). Include manufacturer's cut sheet for any new lighting fixtures and information detailing how it will be attached to the building's facade.
Alt	erat	tions: Check N/A if an item in this section does not apply to your project.
		Clear and labeled photographs of the site, especially the area being impacted by the alterations, all sides of the building and any pertinent details.
□ •	V	Manufacturer's specifications for materials to include, but not limited to: roofing, siding, windows, doors, lighting, fencing, HVAC equipment and walls.
V		Drawings accurately representing the changes to the proposed structure, including materials and overall dimensions. Drawings must be to scale.
		An official survey plat showing the proposed locations of HVAC units, fences, and sheds. Historic elevations or photographs should accompany any request to return a structure to an earlier appearance.

ALL	APPLICATIONS: Please read and check that you have read and understand the following items:
	I have submitted a filing fee with this application. (Checks should be made payable to the City of Alexandria. Please contact staff for assistance in determining the appropriate fee.)
	I understand the notice requirements and will return a copy of the three respective notice forms to BAR staff at least five days prior to the hearing. If I am unsure to whom I should send notice I will contact Planning and Zoning staff for assistance in identifying adjacent parcels.
\mathbf{A}_{μ}	I, the applicant, or an authorized representative will be present at the public hearing.
\checkmark	I understand that any revisions to this initial application submission (including applications deferred for restudy) must be accompanied by the BAR Supplemental form and 3 sets of revised materials.

BAR Case # _____

The undersigned hereby attests that all of the information herein provided including the site plan, building elevations, prospective drawings of the project, and written descriptive information are true, correct and accurate. The undersigned further understands that, should such information be found incorrect, any action taken by the Board based on such information may be invalidated. The undersigned also hereby grants the City of Alexandria permission to post placard notice as required by Article XI, Division A, Section 11-301(B) of the 1992 Alexandria City Zoning Ordinance, on the property which is the subject of this application. The undersigned also hereby authorizes the City staff and members of the BAR to inspect this site as necessary in the course of research and evaluating the application. The applicant, if other than the property owner, also attests that he/she has obtained permission from the property owner to make this application.

APPLICANT OR AUTHORIZED AGENT:

Signature	E Br	ian Taylor	
Printed N		Brian Taylor	
Date:	07/22	2/21	

OWNERSHIP AND DISCLOSURE STATEMENT Use additional sheets if necessary

(Jse additional sheets if necessar	у
an interest in the applicant, ur case identify each owner of n	nddress and percent of ownership nless the entity is a corporat nore than three percent. The te interest held at the time of the cation.	ion or partnership, in which erm ownership interest shall
Name	Address	Percent of Ownership
1. AT&T Mobility	7150 Standard Drive	100%
2.		
3.		
an interest in the property locate entity is a corporation or partner percent. The term ownership in time of the application in the rea	ship, in which case identify each terest shall include any legal or e al property which is the subject of	(address), unless the owner of more than three quitable interest held at the the application.
Name	Address	Percent of Ownership
1. Dominion Energy	220 N Washington St	100%
2.		
3.		
ownership interest in the applicationship business or financial relationship existing at the time of this applications.	onships. Each person or entity list ant or in the subject property is rep, as defined by Section 11-350 cation, or within the12-month perior of the Alexandria City Council, as of Architectural Review.	equired to disclose any of the Zoning Ordinance, od prior to the submission of
Name of person or entity	Relationship as defined by Section 11-350 of the Zoning Ordinance	Member of the Approving Body (i.e. City Council, Planning Commission, etc.)
^{1.} Brian Taylor	N/A	N/A
2.		
3.		
	relationships of the type descr ion and before each public hea	
As the applicant or the applican the information provided above	t's authorized agent, I hereby attoris true and correct.	est to the best of my ability that
7/22/2o2ı Brian Taylo		Taylor

Signature

Printed Name

Date




FA # 14857031 / SITE ID # 269178 CRAN_RWSH_ALEXA_045G

711 WILKES STREET ALEXANDRIA, VA 22314











CRAN_RWSH_ALEXA_045G NODE FA #: 14857031 / HUB FA #: 14510358 / USID #: 269178 711 WILKES STREET ALEXANDRIA, VA 22314









CRAN_RWSH_ALEXA_045G



NODE FA #: 14857031 HUB FA #: 14510358 USID #: 269178 **432 SOUTH COLUMBUS STREET ALEXANDRIA, VA 22314**

DOMINION POLE ID# C1014 TG76

VICINITY MAP

PROJECT SUMMARY

SITE NAME: CRAN_RWSH_ALEXA_045G

> **432 SOUTH COLUMBUS STREET** ALEXANDRIA, VA 22314

I ATITLIDE: 38 80069° N

LONGITUDE: -77.04874° W

COUNTY: ALEXANDRIA CITY COMMERCIAL

POWER COMPANY: DOMINION ENERGY

FIBER COMPANY: VERIZON

SITE LOCATION: RIGHT-OF-WAY (R.O.W)

USE & OCCUPANCY GROUP:

SITE ADDRESS:

GROUND ELEVATION:

WSS (HAPCO METAL POLE)

STRUCTURAL OWNER: DOMINION ENERGY

AUSTIN GORE

3072 CENTERVILLE ROAD HERNDON, VA 20171

4513708 NJUNS #:

PROJECT TEAM

APPLICANT:

AT&T MOBILITY 7150 STANDARD DRIVE

HANOVER, MD 21076 SEAN MITCHELL CONTACT:

SMARTI INK PROJECT MANAGEMENT FIRM

1362 MELLON ROAD, SUITE 140

HANOVER, MD 21076

CONTACT: PHONE: 410-582-8043 x133

TRYLON TSF

CONTACT: 1-855-669-5421

CODE COMPLIANCE

ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES:

BUILDING/DWFLLING IBC 2015

2012 NFPA 101, LIFE SAFETY CODE

SCALE: 1" = 4000'-0" PROJECT DESCRIPTION

THE PROPOSED AT&T PROJECT INCLUDES:

- REPLACE EXISTING LIGHT POLE WITH PROPOSED WSS (HAPCO
- METAL POLE)
 INSTALL PROPOSED LUMINAIRE
- INSTALL PROPOSED 200 AMP METER/100 AMP DISCONNECT COMBO
- INSTALL RF HYBRID CABLE INSIDE METAL STREET LIGHT
- INSTALL POLE TOP MOUNTING KIT INSTALL EQUIPMENT CONCEALMENT SHROUD
- INSTALL (1) RRH UNITS INSIDE NEW CONCEALMENT SHROUD INSTALL GALTRONICS OMNI ANTENNA
- **INSTALL 5G ANTENNAS** INSTALL JUMPERS FROM (1) RRH UNITS TO NEW ANTENNA

DO NOT SCALE DRAWINGS

ALL DRAWINGS CONTAINED HEREIN ARE FORMATTED FOR 11x17. CONTRACTOR SHALL VERIFY ALL PLANS AND EXISTING DIMENSIONS AND CONDITIONS ON THE JOB SITE AND OF ANY DISCREPANCIES REFORE PROCEEDING WITH THE WORK OR BE RESPONSIBLE FOR SAME.

SEE SHEET GN-1 FOR ADDITIONAL CONSTRUCTION NOTES

SHEET #	SHEET DESCRIPTION		
T-1	TITLE SHEET		
T-1 GN-1	GENERAL NOTES		
ROW	RIGHT OF WAY SURVEY		
SP-1	SITE PLAN		
C-1	EXISTING ELEVATION VIEW		
C-2	PROPOSED ELEVATION VIEW		
C-3	EQUIPMENT DETAILS		
C-4	EQUIPMENT DETAILS CONT.		
C-5	PLUMBING DIAGRAM		
C-6	HAPCO POLE DETIALS		
C-7	HAPCO POLE DETIALS		
C-8	5G EQUIPMENT DETAILS		
E-1	AC PANEL INFORMATION		
E-2	ELECTRICAL NOTES		
E-3	ELECTRICAL DETAILS		
E-4	ELECTRICAL DETAILS CONT.		
ý.			

DRAWING INDEX

A/E DOCUMENT REVIEW STATUS

П	TITLE		E	SIGNATURE	DATE	
	CARRIER CONSTRUCTION MGR:					
	SMARTLINK PM:					
	RF ENGINEER:					
	ZONING APPROVAL:			L:		
	SITE ACQUISITION:		1			
	PROPERTY OWNER:		t:			
	STATUS CODE:					
1	1 ACCEPTED: WITH OR NO CO		D: WITH OR NO CO	OMMENTS. CONSTRUCTION MAY PROCEED		

NOT ACCEPTED: RESOLVE COMMENTS AND RESUBMIT


ACCEPTANCE DOES NOT CONSTITUTE APPROVAL OF DESIGN, CALCULATIONS, ANALYSIS, TEST METHODS OF MATERIALS DEVELOPED OR SELECTED BY THE SUBCONTRACTOR AND DOES NOT RELIEVE SUBCONTRACTOR FROM FULL COMPLIANCE WITH CONTRACTUAL OBLIGATIONS.



CALL MISS UTILITY (800) 245-4848 **CALL 3 WORKING DAYS BEFORE YOU DIG!**









SUBMITTALS			
REV	DATE	DESCRIPTION	BY
1	05/27/20	CLIENT COMMENTS	DB
\Box			

RELEASED BY MATTHEW JAMERSON 05/27/21



AT&T NEW CRAN BUILD

SITE ADDRESS

CRAN_RWSH_ALEXA_045G **432 SOUTH COLUMBUS ALEXANDRIA, VA 22314**

SHEET TITLE

TITLE SHEET

PROJECT COMPLIANCE NOTES:

- THE PROPOSED FACILITY WILL BE UNMANNED AND DOES NOT REQUIRE POTABLE WATER OR SEWER SERVICE AND IS NOT FOR HUMAN HABITAT. (NO HANDICAP ACCESS IS REQUIRED)
- OCCUPANCY IS LIMITED TO PERIODIC MAINTENANCE AND INSPECTION, APPROXIMATELY 2 TIMES PER MONTH, BY AT&T TECHNICIANS.
- NO NOISE, SMOKE, DUST OR ODOR WILL RESULT FROM THIS PROPOSAL, UNLESS DURING
- OUTDOOR STORAGE AND SOLID WASTE CONTAINERS ARE NOT PROPOSED.
- ALL MATERIAL SHALL BE FURNISHED AND WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE LATEST AT&T SYSTEM GROUNDING STANDARDS. "TECHNICAL SPECIFICATION FOR CONSTRUCTION OF LTE SITES AND WILL FOLLOW AT&T GROUNDING AND BONDING REQUIREMENTS FOR NETWORK FACILITIES AT&T DOC ID ATT-TP-76416 AND AT&T POLICY LETTER ATT-CFM-13002
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR REPAIRING ANY DAMAGE CAUSED DURING CONSTRUCTION OPERATION.
- THE CONTRACTOR SHALL REMOVE ALL TRASH AND DEBRIS FROM THE SITE ON A DAILY BASIS.
- INFORMATION SHOWN ON THESE DRAWINGS WAS OBTAINED FROM DRAWINGS PROVIDED BY THE APPLICANT REPRESENTATIVE. THE CONTRACTOR SHALL NOTIFY TURF VENDOR OF ANY DISCREPANCIES PRIOR TO ORDERING MATERIAL OR PROCEEDING WITH CONSTRUCTION.
- NO ADDITIONAL PARKING IS PROPOSED. EXISTING ACCESS AND PARKING WILL BE USED.
- NO ADDITIONAL LANDSCAPING IS PROPOSED AT THIS SITE.
- ALL COAXIAL CABLE/FIBER AND DC CABLE INSTALLATION IS TO FOLLOW MANUFACTURER'S INSTRUCTION

GREENFIELD GROUNDING NOTES:

ALL GROUND ELECTRODE SYSTEMS (INCLUDING TELECOMMUNICATION, RADIO, LIGHTNING PROTECTION AND AC POWER GES'S) SHALL BE BONDED TOGETHER AT OR BELOW GRADE, BY TWO OR MORE COPPER BONDING CONDUCTORS IN ACCORDANCE WITH THE NEC.

THE SUBCONTRACTOR SHALL PERFORM IFFE FALL-OF-POTENTIAL RESISTANCE TO FARTH TESTING (PER IEEE 1100 AND 81) FOR GROUND ELECTRODE SYSTEMS. THE SUBCONTRACTOR SHALL FURNISH AND INSTALL SUPPLEMENTAL GROUND FLECTRODES AS NEEDED TO ACHIEVE A TEST RESULT OF 5 OHMS OR

THE SUBCONTRACTOR IS RESPONSIBLE FOR PROPERLY SEQUENCING GROUNDING AND UNDERGROUND CONDUIT INSTALLATION AS TO PREVENT ANY LOSS OF CONTINUITY IN THE GROUNDING SYSTEM OR DAMAGE TO THE CONDUIT AND PROVIDE TESTING RESULTS.

METAL CONDUIT AND TRAY SHALL BE GROUNDED AND MADE ELECTRICALLY CONTINUOUS WITH LISTED BONDING FITTINGS OR BY BONDING ACROSS THE DISCONTINUITY WITH #6 AWG COPPER WIRE UL APPROVED GROUNDING TYPE CONDUIT CLAMPS.

METAL RACEWAY SHALL NOT BE USED AS THE NEC REQUIRED EQUIPMENT GROUND CONDUCTOR. STRANDED COPPER CONDUCTORS WITH GREEN INSULATION, SIZED IN ACCORDANCE WITH THE NEC. SHALL BE FURNISHED AND INSTALLED WITH THE POWER CIRCUITS TO BTS EQUIPMENT

EACH BTS CABINET FRAME SHALL BE DIRECTLY CONNECTED TO THE MASTER GROUND BAR WITH GREEN INSULATED SUPPLEMENTAL EQUIPMENT GROUND WIRES, 6 AWG STRANDED COPPER OR LARGER FOR INDOOR BTS: #2 AWG SOLID TINNED COPPER FOR OUTDOOR BTS.

CONNECTIONS TO THE GROUND BAR SHALL NOT BE DOUBLED UP OR STACKED BACK TO BACK CONNECTIONS ON OPPOSITE SIDE OF THE GROUND BAR ARE PERMITTED

ALL EXTERIOR GROUND CONDUCTORS BETWEEN EQUIPMENT/GROUND BARS AND THE GROUND RING SHALL BE #2 AWG SOLID TINNED COPPER UNLESS OTHERWISE INDICATED

ALUMINUM CONDUCTOR OR COPPER CLAD STEEL CONDUCTOR SHALL NOT BE USED FOR GROUNDING CONNECTIONS.

USE OF 90° BENDS IN THE PROTECTION GROUNDING CONDUCTORS SHALL BE AVOIDED WHEN 45° BENDS CAN BE ADEQUATELY SUPPORTED.

EXOTHERMIC WELDS SHALL BE USED FOR ALL GROUNDING CONNECTIONS BELOW GRADE.

ALL GROUND CONNECTIONS ABOVE GRADE (INTERIOR AND EXTERIOR) SHALL BE FORMED USING HIGH

COMPRESSION GROUND CONNECTIONS MAY BE REPLACED BY EXOTHERMIC WELD CONNECTIONS.

ICE BRIDGE BONDING CONDUCTORS SHALL BE EXOTHERMICALLY BONDED OR BOLTED TO THE BRIDGE AND THE TOWER GROUND BAR

APPROVED ANTIOXIDANT COATINGS (I.E. CONDUCTIVE GEL OR PASTE) SHALL BE USED ON ALL COMPRESSION AND BOLTED GROUND CONNECTIONS.

ALL EXTERIOR GROUND CONNECTIONS SHALL BE COATED WITH A CORROSION RESISTANT MATERIAL

MISCELLANEOUS ELECTRICAL AND NON-ELECTRICAL METAL BOXES, FRAMES AND SUPPORTS SHALL BE BONDED TO THE GROUND RING, IN ACCORDANCE WITH THE NEC.

BOND ALL METALLIC OBJECTS WITHIN 6 FT. OF MAIN GROUND WIRES WITH 1-#2 AWG TIN-PLATED COPPER GROUND CONDUCTOR

GROUND CONDUCTORS USED IN THE FACILITY GROUND AND LIGHTNING PROTECTION SYSTEMS SHALL NOT BE ROUTED THROUGH METALLIC OBJECTS THAT FORM A RING AROUND THE CONDUCTOR. SUCH AS METALLIC CONDUITS, METAL SUPPORT CLIPS OR SLEEVES THROUGH WALLS OR FLOORS, WHEN IT IS REQUIRED TO BE HOUSED IN CONDUIT TO MEET CODE REQUIREMENTS OR LOCAL CONDITIONS. NON-METALLIC MATERIAL SUCH AS PVC PLASTIC CONDUIT SHALL BE USED. WHERE USE OF METAL CONDUIT IS UNAVOIDABLE (E.G., NONMETALLIC CONDUIT PROHIBITED BY LOCAL CODE) THE GROUND CONDUCTOR SHALL BE BONDED TO EACH END OF THE METAL CONDUIT

ELECTRICAL INSTALLATION NOTES:

ALL ELECTRICAL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS, NEC AND ALL

CONDUIT ROUTINGS ARE SCHEMATIC. SUBCONTRACTOR SHALL INSTALL CONDUITS SO THAT ACCESS TO EQUIPMENT IS

WIRING, RACEWAY & SUPPORT METHODS AND MATERIALS SHALL COMPLY WITH THE REQUIREMENTS OF THE NEC.

ALL CIRCUITS SHALL BE SEGREGATED AND MAINTAIN MINIMUM CABLE SEPARATION AS REQUIRED BY THE NEC.

CABLES SHALL NOT BE ROUTED THROUGH LADDER-STYLE CABLE TRAY RUNGS.

EACH END OF EVERY POWER, POWER PHASE CONDUCTOR (I.E., HOTS), GROUNDING AND T1 CONDUCTOR AND CABLE SHALL BE LABELED WITH COLOR-CODED INSULATION OR ELECTRICAL TAPE (3M BRAND, 1/2" PLASTIC ELECTRICAL TAPE WITH UV PROTECTION, OR APPROVED EQUAL), THE IDENTIFICATION METHOD SHALL CONFORM WITH NEC AND OSHA

ALL ELECTRICAL COMPONENTS SHALL BE CLEARLY LABELED WITH PLASTIC TAPE PER COLOR SCHEDULE. ALL EQUIPMENT SHALL BE LABELED WITH THEIR VOLTAGE RATING. PHASE CONFIGURATION, WIRE CONFIGURATION, POWER OR AMPACITY RATING AND BRANCH CIRCUIT ID NUMBERS (I.E. PANEL BOARD AND CIRCUIT ID'S).

PANEL BOARDS (ID NUMBERS) AND INTERNAL CIRCUIT BREAKERS (CIRCUIT ID NUMBERS) SHALL BE CLEARLY LABELED WITH PLASTIC LABELS.

ALL TIE WRAPS SHALL BE CUT FLUSH WITH APPROVED CUTTING TOOL TO REMOVE SHARP EDGES.

POWER, CONTROL AND EQUIPMENT GROUND WIRING IN TUBING OR CONDUIT SHALL BE SINGLE CONDUCTOR (#14 AWG OR LARGER), 600 V, OIL RESISTANT THHN OR THWN-2, CLASS B STRANDED COPPER CABLE RATED FOR 90° C (WET & DRY) OPERATION LISTED OR LABELED FOR THE LOCATION AND RACEWAY SYSTEM USED UNLESS OTHERWISE SPECIFIED.

SUPPLEMENTAL EQUIPMENT GROUND WIRING LOCATED INDOORS SHALL BE SINGLE CONDUCTOR (#6 AWG OR LARGER). 600V. OIL RESISTANT THHN OR THWN-2 GREEN INSULATION CLASS B STRANDED COPPER CABLE RATED FOR 90° C (WET AND DRY) OPERATION LISTED OR LABELED FOR THE LOCATION AND RACEWAY SYSTEM USED UNLESS OTHERWISE

POWER AND CONTROL WIRING, NOT IN TUBING OR CONDUIT, SHALL BE MULTI-CONDUCTOR, TYPE TC CABLE (#14 AWG OR LARGER), 600 V. OIL RESISTANT THHN OR THWN-2, CLASS B STRANDED COPPER CABLE RATED FOR 90° C (WET AND DRY) OPERATION WITH OUTER JACKET LISTED OR LABELED FOR THE LOCATION USED UNLESS OTHERWISE SPECIFIED

ALL POWER AND GROUNDING CONNECTIONS SHALL BE CRIMP-STYLE, COMPRESSION WIRE LUGS AND WIRE NUTS BY THOMAS AND BETTS (OR APPROVED EQUAL). LUGS AND WIRE NUTS SHALL BE RATED FOR OPERATION AT NO LESS THAN 75° C (90° C IF AVAILABLE)

RACEWAY AND CABLE TRAY SHALL BE LISTED OR LABELED FOR ELECTRICAL USE IN ACCORDANCE WITH NEMA, UL, ANSI/IEEE AND NEC.

ELECTRICAL METALLIC TUBING (EMT) OR RIGID NONMETALLIC CONDUIT (I.E. RIGID PVC SCHEDULE 40 OR RIGID PVC SCHEDULE 80 FOR LOCATIONS SUBJECT TO PHYSICAL DAMAGE) SHALL BE USED FOR EXPOSED INDOOR LOCATIONS.

ELECTRICAL METALLIC TUBING (EMT), ELECTRICAL NONMETALLIC TUBING (ENT) OR RIGID NONMETALLIC CONDUIT (RIGID PVC, SCHEDULE 40) SHALL BE USED FOR CONCEALED INDOOR LOCATIONS.

GALVANIZED STEEL INTERMEDIATE METALLIC CONDUIT (IMC) SHALL BE USED FOR OUTDOOR LOCATIONS ABOVE GRADE

RIGID NONMETALLIC CONDUIT (I.E. RIGID PVC SCHEDULE 40 OR RIGID PVC SCHEDULE 80) SHALL BE USED UNDERGROUND; DIRECT BURIED, IN AREAS OF OCCASIONAL LIGHT VEHICLE TRAFFIC OR ENCASED IN REINFORCED CONCRETE IN AREAS OF HEAVY VEHICLE TRAFFIC.

LIQUID-TIGHT FLEXIBLE METALLIC CONDUIT (LIQUID-TITE FLEX) SHALL BE USED INDOORS AND OUTDOORS, WHERE VIBRATION OCCURS OR FLEXIBILITY IS NEEDED

CONDUIT AND TUBING FITTINGS SHALL BE THREADED OR COMPRESSION-TYPE AND APPROVED FOR THE LOCATION

CABINETS, BOXES AND WIRE WAYS SHALL BE LABELED FOR ELECTRICAL USE IN ACCORDANCE WITH NEMA, UL, ANSI/IEEE AND NEC

WIREWAYS SHALL BE EPOXY-COATED (GRAY) AND INCLUDE A HINGED COVER, DESIGNED TO SWING OPEN DOWNWARDS; SHALL BE PANDUIT TYPE E (OR APPROVED EQUAL); AND RATED NEMA 1 (OR BETTER)

EQUIPMENT CABINETS, TERMINAL BOXES, JUNCTION BOXES AND PULL BOXES SHALL BE GALVANIZED OR EPOXY-COATED SHEET STEEL. SHALL MEET OR EXCEED UL 50 AND RATED NEMA 1 (OR BETTER) INDOORS OR NEMA 3R (OR BETTER)

METAL RECEPTACLE SWITCH AND DEVICE BOXES SHALL BE GALVANIZED EPOXY-COATED OR NON-CORRODING: SHALL MEET OR EXCEED UL 514A AND NEMA OS 1; AND RATED NEMA 1 (OR BETTER) INDOORS OR WEATHER PROTECTED (WP OR RETTER) OUTDOORS

NONMETALLIC RECEPTACLE, SWITCH AND DEVICE BOXES SHALL MEET OR EXCEED NEMA OS 2; AND RATED NEMA 1 (OR BETTER) INDOORS OR WEATHER PROTECTED (WP OR BETTER) OUTDOORS.

THE SUBCONTRACTOR SHALL NOTIFY AND OBTAIN NECESSARY AUTHORIZATION FROM THE CONTRACTOR BEFORE COMMENCING WORK ON THE AC POWER DISTRIBUTION PANELS.

THE SUBCONTRACTOR SHALL PROVIDE NECESSARY TAGGING ON THE BREAKERS, CABLES AND DISTRIBUTION PANELS IN ACCORDANCE WITH THE APPLICABLE CODES AND STANDARDS TO SAFEGUARD AGAINST LIFE AND PROPERTY

INSTALL PLASTIC LABEL ON THE METER CENTER TO SHOW "AT&T WIRELESS"

PROJECT GENERAL NOTES:

- OR THE PURPOSE OF CONSTRUCTION DRAWING, THE FOLLOWING DEFINITIONS SHALL APPLY: CONTRACTOR-
- SUBCONTRACTOR- GENERAL CONTRACTOR (CONSTRUCTION)
- OWNER- AT&T
- OEM- ORIGINAL EQUIPMENT MANUFACTURER
- PRIOR TO THE SUBMISSION OF BIDS, THE BIDDING SUBCONTRACTOR SHALL VISIT THE CELL SITE TO FAMILIARIZE WITH THE EXISTING CONDITIONS AND TO CONFIRM THAT THE WORK CAN BE ACCOMPLISHED AS SHOWN ON THE CONSTRUCTION DRAWINGS ANY DISCREPANCY FOUND SHALL BE BROUGHT TO THE ATTENTION OF CONTRACTOR.
- ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES. SUBCONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE
- DRAWINGS PROVIDED HERE ARE NOT TO SCALE AND ARE INTENDED TO SHOW OUTLINE ONLY.
- UNLESS NOTED OTHERWISE THE WORK SHALL INCLUDE FURNISHING MATERIALS. FOUIPMENT APPURTENANCES AND LABOR NECESSARY TO COMPLETE ALL INSTALLATIONS AS INDICATED ON
- "KITTING LIST" SUPPLIED WITH THE BID PACKAGE IDENTIFIES ITEMS THAT WILL BE SUPPLIED BY CONTRACTOR. ITEMS NOT INCLUDED IN THE BILL OF MATERIALS AND KITTING LIST SHALL BE SUPPLIED BY THE SUBCONTRACTOR.
- THE SUBCONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE
- IF THE SPECIFIED EQUIPMENT CAN NOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE SUBCONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION FOR APPROVAL BY THE
- SUBCONTRACTOR SHALL DETERMINE ACTUAL ROUTING OF CONDUIT, POWER AND T1 CABLES. GROUNDING CABLES AS SHOWN ON THE POWER, GROUNDING AND TELCO PLAN DRAWINGS.
- THE SUBCONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT SUBCONTRACTOR'S EXPENSE TO THE SATISFACTION OF OWNER.
- 11. SUBCONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS SUCH AS COAXIAL CARLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY ANTENNAS REMOVED SHALL BE RETURNED TO THE OWNER'S DESIGNATED LOCATION.
- 12. SUBCONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION.
- 13. CONSTRUCTION SHALL COMPLY WITH SPECIFICATION 24782-000-3APS-A00Z-00002, "GENERAL CONSTRUCTION SERVICES FOR CONSTRUCTION OF AT&T GSM SITES".

ABBREVIATIONS AND SYMBOLS:

ABBREVIATIONS:

ABOVE GRADE LEVEL BASE TRANSCEIVER STATION BTS EXISTING (E)

N.T.S. NOT TO SCALE REF REFERENCE RADIO FREQUENCY RF T.B.D. TO BE DETERMINED T.B.R. TO BE RESOLVED

RBS

TYPICAL REQ REQUIRED EGR EQUIPMENT GROUND RING AWG AMERICAN WIRE GAUGE MASTER GROUND BAR MGB **EOUIPMENT GROUND**

BARE COPPER WIRE SIAD SMART INTEGRATED ACCESS DEVICE GEN GENERATOR IGR INTERIOR GROUND RING (HALO) RADIO BASE STATION

SYMBOLS:

SOLID GROUND BUS BAR

S/N SOLID NEUTRAL BUS BAR

SUPPLEMENTAL GROUND CONDUCTOR

2-POLE THERMAL-MAGNETIC CIRCUIT **BRFAKER**

SINGLE-POLE THERMAL-MAGNETIC CIRCUIT BREAKER

CHEMICAL GROUND ROD \otimes **TEST WELL**

 \Box DISCONNECT SWITCH

MFTFR







SUBMITTALS			
REV	DATE	DESCRIPTION	BY
1	05/27/20	CLIENT COMMENTS	DB
\vdash			
$\overline{}$			$\overline{}$

RELEASED BY 05/27/21 MATTHEW JAMERSON



BEARING THE SEAL OF A LICENSED ENGINEER OR LAI SURVEYOR IS A VIOLATION OF LOCAL LAW FESSIONAL CERTIFICATION. I HEREBY CERTIFY THA

SITE INFORMATION


AT&T NEW CRAN BUILD

SITE ADDRESS

CRAN RWSH ALEXA 045G **432 SOUTH COLUMBUS** STREET **ALEXANDRIA, VA 22314**

SHEET TITLE

GENERAL NOTES









		SUBMITTALS			
	REV	/ DATE	DESCRIPTION	BY	
	1	05/27/20	CLIENT COMMENTS	DB	
Ш					

RELEASED BY DATE

MATTHEW JAMERSON 05/27/21



UNAUTHORIZED ALTERATION OR ADDITIONS TO A PL BEARING THE SEAL OF A LICENSED ENGINEER OR LAN SURVEYOR IS A VIOLATION OF LOCAL LAW

PROFESSIONAL CERTIFICATION. I HEREBY CERTIFY TI
THESE DOCUMENTS WERE PREPARED OR APPROVED
ME, AND THAT I AM A DULY LICENSED PROFESSIONA
ENGINEER UNDER THE LAWS OF THE STATE OF VIRGI
LICENSE NO. 0402061949 EVP. 03/12/2022

ORIGINAL SIZE IN INCHE

AT&T NEW CRAN BUILD

SITE ADDRESS


CRAN_RWSH_ALEXA_045G 432 SOUTH COLUMBUS STREET ALEXANDRIA, VA 22314

SHEET TITLE

RIGHT OF WAY SURVEY

SHEET NUMBER








SHEET NUMBER


SP-1


DATE 05/27/21





EXISTING CONDITIONS PHOTO 1 SCALE: 3/16" = 1'-0"





























ITEM NO.	PART NUMBER	DESCRIPTION	QTY
1	860644741	MC TOP MOUNTING PLATE	1
2	860644742	ANTENNA MOUNT BRACKET, TRIPOD	1
3	100521-47	WSHR,FLAT,M12,13X28X2.5,STL,GALV	21
4	600679-4	SPACER TUBE	3
5	626852-1	PIPE CLAMP BRACKET,150X93.6X52MM	3
6	100526-45	NUTS,HEX,M12,STL,GALV	30
7	100555-81	STUD,THREADED,M12-1.75,245,STL,GALV	3
8	100555-82	STUD,THREADED,M12-1.75,215,STL,GALV	3
9	100534-265	SCR,HCS,HEX,M12X45,STL,GALV	3

NOTE:

CONTRACTOR TO USE COMMSCOPE POLE TOP MOUNTING KIT OR EQUIVALENT






COMMSCOPE POLE TOP MOUNTING KIT C-3 NOT TO SCALE


⊗ smartlinl SUBMITTALS REV DATE DESCRIPTION 05/27/20 CLIENT COMMENTS RELEASED BY MATTHEW JAMERSON AT&T NEW CRAN BUILD SITE ADDRESS CRAN_RWSH_ALEXA_045G 432 SOUTH COLUMBUS STREET **ALEXANDRIA, VA 22314** SHEET TITLE **EQUIPMENT DETAILS** SHEET NUMBER

05/27/21




VERIFIED BY GC PRIOR TO ORDERING FIBER EXTENSION CABLE. **TRANSPORT CONNECTION DETAIL** C-4 NOT TO SCALE

TRANSPORT CONNECTION TYPE TO BE




ANTENNA DETAIL C-4 NOT TO SCALE




GALTRONICS ANTENNA: MODEL: GQ2418-B6941 DIMENSIONS: 16"x24.0" WEIGHT: 26.3 LBS


воттом VIEW



APPROVED CABLE MATRIX
C-4 NOT TO SCALE




4 ANTENNA SHROUD DETAIL
C-4 NOT TO SCALE




DATE

05/27/21




PLUMBING DIAGRAM
C-5 NOT TO SCALE



FIBER P-TOUCH TAG DETAIL (TYPICAL)
C-5 NOT TO SCALE

	ANTENNA SCHEDULE								
SECTOR	STATUS	ANTENNA MANUFACTURER	ANTENNA MODEL	ANTENNA DIMENSIONS	RAD CENTER	TIP HEIGHT	AZIMUTH	RRH MODEL	CABLE LENGTH
ALPHA 1	PROPOSED	GALTRONICS	GQ2418-B6941	24.0"x16"Ø	37'-05"	38'-05"	0°-359°	AHFB B25 (PCS) - CEQ.20198 AHIB B66 (AWS) - CEQ.20197 AZRB B46 (LAA) - CEQ.20927	50'-00"
ALPHA 2	PROPOSED	NOKIA	5G-NR AEWD	12.75"H x 9.25"W x 6"D	25'-00"	25'-06"	0°-359°	INTEGRATED	50'-00"





- GENERAL NOTES:

 1. THE POLE HAS THREE INTERNAL CHAMBERS.
 - CHAMBER "A" IS FOR WIRELESS PROVIDER'S CONDUCTORS (COMMUNICATION AND POWER). - CHAMBER "B" IS FOR STREETLIGHT CONDUCTORS.

 - CHAMBER "C" IS FOR STREETLIGHT CONDUCTORS TO SECOND STREETLIGHT IF NECESSARY.
- THE STANDARD SETTING DEPTH IS 8 FT. DEEP.
 USE SELECT BACKFILL (#57 STONE) INSTALLED IN 24" AUGER HOLE.
 - BACKFILL TO BE COMPACTED IN 6" LAYERS.

- 3. FOR SOFT SOILS, THE POLE MAY BE INSTALLED IN A PIPE PILE.

 THE STANDARD PIPE PILE IS 30 INCHES IN DIAMETER AND 15 FT. LONG.

 THE PIPE PILE IS TO BE VIBRATED INTO THE GROUND.
- THE TOP OF THE PIPE PILE TO BE 6" BELOW GRADE TO ALLOW LANDSCAPING (GRASS).
- STOCK NUMBER 42407588.
 ALL POWER CONDUCTORS TO ORIGINATE FROM A DIVIDED SPLICE BOX ADJACENT TO THE POLE.
 - COMPANY OWNED CONDUCTORS TO TERMINATE IN SIDE MARKED "DOMINION".

 - DOMINION COVER HAS PENTA HEAD BOLTS.
 WIRELESS PROVIDER'S POWER CONDUCTORS TO TERMINATE IN SIDE MARKED "PVT ELECTRIC".
 PVT ELECTRIC COVER HAS STANDARD 9/16" HEX HEAD BOLTS.
- DOMINION TO PUSH CONDUCTORS FORM PRIVATE SIDE INTO DOMINION SIDE AND MAKE CONNECTIONS.
- SPLICE BOX TO BE A MINIMUM OF 3 FEET FROM AUGER HOLE
- 5. THE METER BASE / DISCONNECT COMBO UNIT PROVIDES FOR 100 AMP SERVICE. - POLE INCLUEDS A BRACKET 5' ABOVE GROUNDLINE FOR MOUNTING THE RAYCAP
- METERBASE/ LOAD CENTER UNIT.
- LINE SIDE CONDUCTORS ENTER REAR KNOCKOUT OF LOWER COMPARTMENT. (#6 AWG - 4/0)
- LOAD SIDE CONDUCTORS ENTER REAR KNOCKOUTS OF UPPER COMPARTMENT.
- 6. MAXIMUM 20 FOOT ALUMINUM ELLIPTICAL BRACKET.

 STREETLIGHT BRACKETS ARE CLAMPED TO THE POLE
- DOUBLE BRACKET MAY BE MOUNTED BACK TO BACK
- STREETLIGHT CONDUCTOR TO BE FUSED IN SPLICE BOX WITH 15 AMP FUSE.

 USE SUBMERSIBLE STREETLIGHT FUSE KIT 66265000.
- 8. INSTALL FULL GRID ADDRESS 4 FEET ABOVE GRADE FACING THE STREET.

 POLE SHALL BE IDENTIFIED BY APPLYING ADHESIVE STENCILING DIRECTLY TO POLE AFTER CLEANING THE AREA WITH A DEGREASER.
- SERVICE TO METERBASE REQUIRES SEPARATE SECONDARY FROM TRANSFORMER TO THE SPLICE BOX.

 ANTENNA SERVICE REQUIRES 120/240 VOLTS (OR 120/208 VOLTS).
- 10. TO ELIMINATE RF EXPOSURE, POWER TO THE ANTENNA MUST BE TURNED OFF PRIOR TO WORKING ON THE STREETLIGHT.
- THE COMPANY MUST HAVE ACCESS TO THE DISCONNECT AT ALL TIMES. IF THE DISCONNECT MUST BE LOCKED, THE LOCK MUST BE AN EXPENDABLE TWIST OFF TYPE LOCK.


 11. ALL GROUNDED CONDUCTORS TO BE BONDED TOGETHER.


 12. MAXIMUM GROUNDLINE MOMENT OF 50 FOOT POLE IS 51,612 FT. LBS.
- MAXIMUM SHEAR IS 1975 LBS.


- REQUIREMENTS FOR ANTENNA ATTACHMENTS:
- WIRELESS PROVIDER TO SUBMIT EQUIPMENT SPECIFICATIONS FOR MANUFACTURER'S APPROVAL. RF HAZARD ANALYSIS TO BE SUBMITTED BY QUALIFIED ENGINEER.
- RF NOTICE SIGN TO BE INSTALLED ABOVE STREETLIGHT BRACKET.

 RF NOTICE SIGN TO BE FACING THE STREETLIGHT.

 POLES WITH TWO STREETLIGHT BRACKETS MUST HAVE A RF NOTICE SIGN ON EACH SIDE OF THE
- 4. BATTERY BACK-UP FOR ANTENNA SERVICE IS NOT PERMITTED.
- ANTENNA MUST BE ABLE TO BE DE-ENERGIZED BY REMOVING THE METER AND/OR OPENING THE
- 5. AN RY NOTICE SIGN MUST BE INSTALLED ON THE EQUIPMENT CABINET WHICH INCLUDES THE WIRELESS PROVIDER'S NAME AND 24 HOUR CONTACT PHONE NUMBER.
- 6. EQUIPMENT CASES CANNOT UNDULY OBSTRUCT A WALKWAY.
- OTHERWISE 9 FEET OF GROUND CLEARANCE IS REQUIRED OVER PEDESTRIAN WALKWAYS. UNLESS SPECIFIED OTHERWISE, ALL EQUIPMENT TO BE BANDED TO THE POLE.
- THE WIRELESS PROVIDER TO DETERMINE THE NEED FOR PIPE PILES BASE ON SOIL CONDITIONS AND EQUIPMENT TO BE ATTACHED.
- 9. THE RAYCAP METERBASE/DISCONNECT COMBO UNIT TO BE OWNED BY THE WIRELESS PROVIDER.







MOUNTING OF SINGLE BRACKET

MOUNTING OF DOUBLE BRACKET

- PLACE THE FRONT BAND/TRUSS ARM ONTO THE POLE, LINING UP THE
 CENTER OF THE UPPER ARM MEMBER WITH THE WIRE HOLE ON THE POLE.
- WITH THE ARM IN PLACE, PLACE THE BACK BANDS ON THE OPPOSITE SIDE OF THE POLE AND LINE THEM UP WITH THE FRONT BANDS.
- 3. ONCE THE BOLT HOLES ON THE BANDS ARE LINED UP, INSERT THE BOLTS. USE THE INCLUDED WASHERS.
- 4. WITH THE BOLT RUNNING THROUGH BOTH BANDS, FASTEN THEM TOGETHER USING THE SUPPLIED HEX NUTS. USE THE INCLUDED WASHERS

COMPATIBLE UNIT	STOCK NO.	LENGTH	RISE	EPA	WEIGHT
BKTTB8FT	42341101	7'-6"	3'-3"	2.48 SQ.FT.	20.4 LBS.
BKTTB10FT	42341102	9'-6"	3'-3"	2.74 SQ.FT.	25.5 LBS.
BKTTB12FT	42341103	11'-6"	3'-3"	2.98 SQ.FT.	31.9 LBS.
BKTTB16FT	42341104	14'-6"	3'-3"	3.47 SQ.FT.	43.4 LBS.
BKTTB20FT	42341052	20'	2'-8"	4.34 SQ.FT.	62.3 LBS.

HAPCO POLE STREET LIGHT BRACKET DETAIL C-6 NOT TO SCALE







SUBMITTALS					
REV	DATE	DESCRIPTION	BY		
1	05/27/20	CLIENT COMMENTS	DB		
\Box					

RELEASED BY 05/27/21 MATTHEW JAMERSON



BEARING THE SEAL OF A LICENSED ENGINEER OR LAN SURVEYOR IS A VIOLATION OF LOCAL LAW

SITE INFORMATION

AT&T NEW CRAN BUILD

SITE ADDRESS


CRAN_RWSH_ALEXA_045G **432 SOUTH COLUMBUS** STREET **ALEXANDRIA, VA 22314**

SHEET TITLE

HAPCO METAL **POLE DETAILS**

SHEET NUMBER





GENERAL NOTES:

- 1. CLEAN OUT PIPE PILE TO REQ'D DEPTH: 7'-6" + 2'-0" MIN.
- ADD SPECIFIED COMPACTED STONE BACKFILL MINIMUM OF 2'-0" BELOW THE BASE
- BACKFILL MATERIAL SHALL BE PLACED IN 4" LIFTS. EACH LAYER SHALL BE COMPACTED USING MECHANICAL OR PNEUMATIC TAMPERS. A MINIMUM OF 3 PASSES SHALL BE MADE OVER EACH LAYER. ADDITIONAL PASSES ARE TO BE MADE IF DISPLACEMENT OF THE BACK FILL IS STILL EVIDENT ON THE OPERATOR TO MAINTAIN DOWNWARD PRESSURE ON THE UNI8T AT ALL TIMES.

1 HAPCO POLE INSTALLATION DETAIL

C-7 NOT TO SCALE


- NOTES:

 1. STEEL PIPE PILE SHALL CONFORM TO THE LATEST EDITION OF ASTM SPECIFICATION A-252
 "WELDED AND SEAMLESS STEEL PIPE PILES". STEEL PLATE FOR PILE FABRICATION TO HAVE A
 MINIMUM Fy=45 KSI. CORROSION RESISTANT STEEL TYPES SUCH AS ASTM A242, A588, A871
- MINIMOM FY=45 NSI. CURROUSIN RESISTANT STEEL TIPES SUCH AS ASTM A242, A386, A671 ETC. ARE NOT TO BE USED.

 2. PILES MAY BE FABRICATED AS ROUND, 12—SIDED OR 16—SIDED SHAPES. DIAMETER REFERENCE FOR 12—SIDED AND 16—SIDED SHAPES IS TO BE MEASURED FROM FLAT TO FLAT.


 3. ALL WELDING TO BE IN ACCORDANCE WITH THE LATEST EDITION OF AWS D1.1. USE APPROPRIATE ELECTRODE FOR STEEL GRADE TYPES, (E70 MINIMUM). CIRCUMFERENTIAL AND LONGITUDINAL WELDS TO BE COMPLETE—PENETRATION.
- 4. PIPE PILE VENDOR SHALL SUPPLY THE 1" DIA. HEAVY HEX GALVANIZED NUTS AND THREE 1"
 DIA. GALVANIZED LEVELING BOLTS AND ENSURE THESE NUTS AND BOLTS ARE COMPATIBLE WITH
 EACH OTHER. LEVELING BOLTS MAY BE FABRICATED OR AN ALL-THREAD BOLT WITH THE BOLT THREADS EXTENDING TO WITHIN 1/2" OF THE BOLT HEAD MAY BE USED. THIS HARDWARE
- SHALL BE HOT DIP GALVANIZED.


 AFTER FABRICATION, HOT DIP GALVANIZE THE PILE AS SPECIFIED PER ASTM A123. PROVIDE ADDITIONAL HOLES IF NEEDED FOR HANDLING DURING GALVANIZING.
- THE THREE 1" DIA. HEAVY HEX NUTS ON THE PILE MUST BE RE-TAPPED AFTER GALVANIZING THE PIPE PILE UNIT. PIPE PILE VENDOR IS RESPONSIBLE TO ENSURE THE LEVELING BOLTS CAN BE THREADED THROUGH EACH RE-TAPPED NUT AND WORKS PROPERLY PRIOR TO SHIPPING THE PILE TO DOMINION.
- 7. THE 1" DIA. LEVELING BOLTS ARE TO BE SHIPPED LOOSE TO PREVENT DAMAGE DURING




ITEM NO.	QUANTITY	PIPE PILE DIA.	TOTAL LENGTH 'E'	WALL THK.	APPX. WT. (LBS) (EACH)
750.00		30" O.D.	16'-0"	3/8"	1,856

STEEL PLATE FOR PILE: Fy = 45 KSI MIN. APPX. PILE WEIGHTS INCLUDE SUPPORT







1" DIA. A307 GALV. TH'D ROD W/HH NUT WELDED ON OR ALL-THREAD BOLT (SEE NOTE 6) THREE (3) BOLTS REQUIRED PER PIPE PILE

ITEM NO.	QUANTITY	LEVELING BOLT LENGTH
781.00		18"


VERIFY THAT LEVELING BOLTS WORK PROPERLY IN 1" DIA. HEAVY HEX NUTS PRIOR TO SHIPPING.

LEVELING BOLT DETAIL

PIPE PILE AND PORTHOLE DETAIL

C-7 NOT TO SCALE







		SUBMITTALS	
REV	DATE	DESCRIPTION	BY
1	05/27/20	CLIENT COMMENTS	DB
\vdash			
$\overline{}$			$\overline{}$

RELEASED BY MATTHEW JAMERSON 05/27/21



BEARING THE SEAL OF A LICENSED ENGINEER OR LAND SURVEYOR IS A VIOLATION OF LOCAL LAW

AT&T NEW CRAN BUILD

SITE ADDRESS

CRAN_RWSH_ALEXA_045G **432 SOUTH COLUMBUS** STREET ALEXANDRIA, VA 22314

SHEET TITLE

HAPCO METAL POLE DETAILS

SHEET NUMBER

PIPE PILE

5G Radio Main Module (39 GHz AEWD)

Ultra-Deployable Medium Power solution deployments

Spec fication ¹	Details
5G Band/Frequency	n260, 37000–40000 MHz
RF Output Power	EIRP 51 dBm
ax Supported Modulation	256 QAM DL / 64 QAM UL
RF Bandwidth	OBW: 800MHz; IBW: 1400MHz ²
Carriers	Up to eight 100MHz 5G NR carriers
Carrier Bandwidth	50, 100, 200 , 400MHz
Physical Size ¹	Dimensions: 363(h) x 283(w) x 173(D) mm Volume: 12L, Weight: 12Kg (with integrated antenna)
Synchronization	via <u>Airscale</u> BBU
Backhaul Port	2 x SFP28 (eCPRI)
Antenna	Configuration: Integrated 2Tx/2Rx 2x128 AE w/2 single polarized 8 x 8 arrays per panel Horizontal Steering Angle :+/-90° Vertical Steering Angle:+/-30° Horizontal BW: 12°, Vertical BW: 9°
Operating Temp	-40°C to +55°C
Input Power	100 - 250 VAC, -40.557 VDC
Pawer Consumption	370W Typ
Other Interfaces	2 status LEDs and interconnect to Supplementary unit
Cooling	Forced Air
Ingress Protection Class	IP65
Surge Protection	Class II 5kA
Installation Options © 2018 Nokia	Wall , Pole, and Strand Specifications are preliminary and subject to change

Medium Power mmWave Radio Module Benefits · Compact form factor enabling mass deployments of 5G-NR (mmWave)

- Main module incl. Antenna for 180° coverage + Extension Antenna module for 360° coverage
- · Wide 1400MHz Instantaneous Bandwidth
- Modular platform that combines with RAP DU Module (ASOD) on site

Extension Module - AEWE



Main Module - AEWD NOKIA **Mounting Kits**

474923A :AMEB AirScale Strap Mount Pole Kit 474941A: AMPD AirScale Tilt Mounting Kit Any size pole up up to 6 inch pole with band straps included. 110 mm max pole size Larger poles require customer to purchase larger band straps to accommodate pole. 090964A 834240A 088748A 089172A

NOKIA - 5G ANTENNA DETAIL C-8 NOT TO SCALE

Ultra-Deplayer e 360° Site Solution AEWD & AEWE




Side view 4-inch pole (Use pole extension for Pole Top Mount)



4-inch pole





Top View Flat Panel Mounted 180° - AWED only



- Quasi omni
- 4 active beamforming antenna array panels providing 360° coverage
- Single cell efficiently sharing resources in coverage areas where required
- Perceived as 4 "virtual" cells
- UE perspective, single cell with 64 beams
- EMS sees this as one cell

5G ANTENNA MOUNTING DETAILS 2 **5G ANTEN** C-8 NOT TO SCALE











SUBMITTALS					
REV	DATE	DESCRIPTION	BY		
1	05/27/20	CLIENT COMMENTS	DB		

RELEASED BY 05/27/21 MATTHEW JAMERSON



AT&T NEW CRAN BUILD

SITE ADDRESS


CRAN_RWSH_ALEXA_045G 432 SOUTH COLUMBUS **ALEXANDRIA, VA 22314**

SHEET TITLE

5G EQUIPMENT DETAILS

SHEET NUMBER

- LINE SIDE CONDUCTORS TO ENTER BOTTOM KNOCKOUT IN REAR (#6 AWG 4/0). LOAD SIDE CONDUCTORS TO ENTER TOP KNOCKOUT IN REAR.
- 120/208 VOLT SERVICE REQUIRES 5TH LUG.
- 120/200 VOLT SERVICE REQUIRES STIL LOG.
 BREAKER INTERRUPTING RATING IS 10,000 AMPS SYMMETRICAL.
 UNIT_ATTACHED TO MOUNTING PLATE WITH EIGHT 5/16" 18NC STAINLESS STEEL
 - SCREWS ARE PROVIDED WITH THE POLE.




100 AMP METER/DISCONNECT COMBO UNIT BY RAYCAP CATALOG NO. RMX-E2C-Z12MS-21NND

RAYCAP METER/DISCONNECT PANEL DETAILS E-1 NOT TO SCALE


- 1. COMPANY CONDUCTORS IN SIDE MARKED "DOMINION"
- 1. COMPANY CONDUCTORS IN SIDE MARKED DOMINION.
 2. CUSTOMER CONDUCTORS IN SIDE MARKED "PVT ELECTRIC".
 3. SPICE BOX NOT CLOSER THAN 3' FROM POLE AUGER HOLE.
 4. STREETLIGHT CONDUCTORS AND CONDUIT TO ENTER POLE CHAMBER "C".

 EXTEND 1" LFNC CONDUIT AT LEAST 12" INTO POLE CHAMBER.
 5. CUSTOMER CONDUCTORS AND CONDUIT TO ENTER POLE CHAMBER "A".
- 6. CUSTOMER TO LEAVE AT LEAST 8' OF CONDUCTOR FOR TERMINATING IN
- CUSIOMER TO LEAVE AT LEAST 8 OF CONDUCTOR FOR TERMINATING IN SPLICE BOX.
 CU SBOX36D IS MATERIAL ONLY.
 IF NEEDED, SERVE SECOND STREETLIGHT WITH SEPARATE CONDUCTORS IN CHAMBER "C".

	1			
KEY	STOCK NO.	DESCRIPTION	QUANTITY	SBOX36D
1	42350224	SPLICE BOX, W/ DIVIDER, 36"x24"x18"	1	1
2	66265000	FUSE, INLINE SUBMERSIBLE	1	-
3	67507400	#4 COPPER, 3 CONDUCTORS	SPECIFY	-
4	42238502	CONNECTOR, #6 - 500 AL/CU, SUBMERSIBLE	3	-
5	SPECIFY	SECONDARY, 3 CONDUCTOR	SPECIFY	-
6	71291500	90 DEG. ELBOW, 2"	2	2
7	71009100	BELL END, 2"	3	3
8	71162000	PVC CONDUIT, 2"	SPECIFY	-
9	57878000	5/8" COPPER CLAD GROUND ROD, 8 FOOT	1	-
10	53711000	#4 COPPER, BARE	20'	-
11	57814000	GROUND ROD CLAMP	1	-
12	65122000	1" LFNC FLEX CONDUIT	SPECIFY	-
13	70200500	#10 COPPER, BLACK	SPECIFY	-
14	70200600	#10 COPPER, WHITE	SPECIFY	-
15	70200700	#10 COPPER, GREEN	SPECIFY	_
16	NA	CUSTOMER OWNED CONDUCTOR AND CONDUIT	NA	_









1. LOAD CENTER IS SUPPLIED WITH MAIN BREAKER ONLY. CONTRACTOR SHALL PROVIDE ALL BRANCH BREAKERS AS INDICATED.

3 RAYCAP METER/DISCONNECT PANEL DETAILS E-1 NOT TO SCALE





BASIC ELECTRICAL NOTES

- THE WORK INCLUDES FURNISHING AND INSTALLING THE MATERIAL, EQUIPMENT AND SYSTEMS COMPLETE AS SPECIFIED AND/OR INDICATED ON THE DRAWINGS. THE ELECTRICAL INSTALLATIONS, WHEN FINISHED, SHALL BE COMPLETE AND COORDINATED AND READY FOR SATISFACTORY SERVICE.
- ALL WORK UNDER THIS CONTRACT SHALL BE DONE IN STRICT ACCORDANCE WITH ALL APPLICABLE MUNICIPAL, STATE, BOCA, AND LOCAL ELECTRICAL CODES THAT GOVERN EACH PARTICULAR TRADE AND THE 2014 NATIONAL ELECTRICAL CODE.
- 3. THE CONTRACTOR SHALL COORDINATE THE ELECTRICAL EQUIPMENT INSTALLATION WITH ALL TRADES.
- 4. THE CONTRACTOR SHALL MAKE APPLICATION AND PAY ALL CHARGES FOR ALL NECESSARY PERMITS, LICENSES, AND INSPECTIONS AS REQUIRED UNDER THE ABOVE CODES. UPON COMPLETION OF THE WORK, THE CUSTOMARY CERTIFICATIONS OF APPROVAL SHALL BE FURNISHED.
- 5. NO MATERIALS OR EQUIPMENT SHALL BE USED IN THE WORK UNTIL APPROVED. ALL MATERIALS SHALL BE U.L. LISTED.
- 6. THE CONTRACTOR SHALL EXAMINE ALL DRAWINGS AND SHALL INSPECT THE EXISTING CONDITIONS OF THE SITE. FAILURE TO COMPLY WITH THIS REQUIREMENT WILL NOT RELIEVE THE CONTRACTOR OF RESPONSIBILITY FOR COMPLYING WITH THE CONTRACTOR DOCUMENTS.
- 7. THE DRAWINGS INDICATE THE GENERAL ARRANGEMENTS OF THE ELECTRICAL INSTALLATIONS. DETAILS OF PROPOSED DEPARTURES DUE TO ACTUAL FIELD CONDITIONS OR OTHER CAUSES SHALL BE SUBMITTED FOR APPROVAL PRIOR TO INSTALLATION. REWORK OF COMPLETED ITEMS DUE TO IMPROPER FIELD COORDINATION SHALL BE AT THE CONTRACTORS EXPENSE
- 8. PROVIDE SUFFICIENT ACCESS AND CLEARANCE FOR ALL ITEMS OF EQUIPMENT REQUIRING SERVICING AND MAINTENANCE.
- 9. THE CONTRACTOR SHALL PERFORM ALL NECESSARY CUTTING AND PATCHING AS REQUIRED TO COMPLETE THE INSTALLATIONS. PATCHING OF WALLS, FLOORS, CEILINGS, ETC. SHALL MATCH THE ADJACENT SURFACES.
- 10. THE CONTRACTOR SHALL PREPARE THREE (3) COPIES OF A RECORD AN INFORMATION BOOKLET. THE BOOKLET SHALL BE BOUND IN A THREE RING LOOSE-LEAD BINDER AND INCLUDE ALL ITEMS OF ELECTRICAL EQUIPMENT.
- 11. UPON COMPLETION OF THE ELECTRICAL INSTALLATION, THE CONTRACTOR SHALL PROVIDE A COMPLETE SET OF PRINTS OF THE ELECTRICAL CONTRACT DRAWINGS WHISH SHALL BE LEGIBLY MARKED IN RED TO SHOW ALL CHANGES AND DEPARTURE OF THE INSTALLATIONS COMPLETED WITH THE ORIGINAL DESIGN. THEY SHALL BE SUITABLE FOR USE IN PREPARATION OF RECORD DRAWINGS.
- 12. GUARANTEE: ALL NEW ELECTRICAL INSTALLATIONS SHALL BE GUARANTEED FOR A PERIOD OF ONE (1) YEAR BEGINNING THE DAY OF THE FINAL ACCEPTANCE OF THE WORK OR BENEFICIALLY OCCUPANCY OF THE OWNER, WHICHEVER OCCURS FIRST. THE ABOVE SHALL NOT IN ANY WAY VOID OR ABROGATED EQUIPMENT MANUFACTURER'S GUARANTEE OR WARRANTY. CERTIFICATES OF GUARANTEE SHALL BE DELIVERED TO THE OWNER. UPON RECEIPT OF THE NOTICE FROM THE OWNER OF FAILURE OF ANY PART OF THE ELECTRICAL INSTALLATION DURING THE GUARANTEE PERIOD, NEW REPLACEMENT PARTS SHALL BE FURNISHED AND INSTALLED PROMPTLY AND AT NO COST TO AT&T.
- 13. ANY ELECTRICAL WORK WHICH WILL INTERFERE WITH THE NORMAL USE OF THE BUILDING IN ANY MANNER SHALL BE DONE AT SUCH TIME OR TIMES AS SHALL BE MUTUALLY AGREED UPON BETWEEN THE CONTRACTOR AND THE AT&T REPRESENTATIVE.
- 14. SUPPORTS, HANGERS, AND FOUNDATIONS: PROVIDE ALL SUPPORTS, HANGERS, BRACES, ATTACHMENTS, AND FOUNDATIONS REQUIRED FOR THE WORK. SUPPORT AND SET THE WORK IN A THOROUGHLY SUBSTANTIAL AND WORKMANLIKE MANNER WITHOUT PLACING STRAINS ON THE MATERIALS, EQUIPMENT, OR THE BUILDING STRUCTURE. SUPPORTS, HANGERS, BRACES AND ATTACHMENTS SHALL BE STANDARD MANUFACTURED ITEMS OR FABRICATED STRUCTURAL STEEL SHAPES.
- 15. THERE SHALL BE NO INTERRUPTION OF POWER TO EXISTING ELECTRICAL SYSTEMS WITHOUT PRIOR CONSENT FROM AT&T. SUCH INTERRUPTIONS SHALL BE KEPT TO A MINIMUM AND SHALL BE SCHEDULED WITH THE OWNER AT LEAST THREE BUSINESS DAYS IN ADVANCE OF THE OUTAGE. ANY COST FOR WORK THAT MUST BE DONE ON AN OVERTIME BASIS SHALL BE INCLUDED IN THE BID.
- 16. MOUNTING AND SUPPORTING OF ALL EQUIPMENT PROVIDED BY THIS CONTRACTOR SHALL BE COORDINATED WITH AT&T IN THE FIELD.
- 17. PROVIDE ALL CUTTING AND PATCHING NECESSARY FOR THE INSTALLATION OF THE ELECTRICAL WORK. ANY DAMAGE DONE TO THE WORK ALREADY IN PLACE BY REASON OF THIS WORK SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE BY A QUALIFIED MECHANIC EXPERIENCED IN SUCH WORK. PATCHING SHALL BE UNIFORMED IN APPEARANCE AND SHALL MATCH THE SURROUNDING SURFACE. ALL PENETRATIONS THROUGH WALLS OF NEW ROOM SHALL BE SEALED WEATHERTIGHT.

SERVICE & DISTRIBUTION

- A. ELECTRICAL SERVICE:
 - 1. ELECTRICAL POWER TO THE NEW EQUIPMENT SHALL BE EXTENDED FROM THE PROPOSED UTILITY COMPANY METER AND PROPOSED SERVICE ENTRANCE RATED LOAD CENTER PANEL MOUNTED ON UTILITY POLE.
- B. COMMUNICATIONS SERVICE:
 - TELEPHONE SERVICES SHALL BE EXTENDED BY THE TELEPHONE COMPANY. PROVIDE SERVICE CONDUITS, BACKBOARDS, SLEEVES, AND OTHER EQUIPMENT SHOWN ON THE DRAWINGS FOR USE BY THE TELEPHONE COMPANY. ALL CHARGES BY THE UTILITY COMPANY SHALL BE PAID BY THE OWNER.
 - 2. ALL ELBOWS IN CONDUITS RUNS SHALL BE WIDE SWEEP FIELD BENDS. INSTALL PULL BOXES AS REQUIRED AND
 WHERE DIRECTED BY THE TELEPHONE COMPANY AND/OR AS REQUIRED BY THE NATIONAL ELECTRIC CODE

BASIC ELECTRICAL MATERIALS & METHODS

A. CONDUIT & BOXES:

- 1. ALL CONDUIT SHALL BE NONMETALLIC ELECTRIC GRADE.
- JUNCTION AND PULL BOXES SHALL BE FURNISHED AND INSTALLED AS SHOWN OR WHERE REQUIRED TO FACILITATE
 PULLING OF WIRES OR CABLES. SUCH BOXES SHALL BE INSTALLED IN ACCESSIBLE LOCATIONS. GASKETED COVER PLATES
 SHALL BE FURNISHED FOR OUTDOOR INSTALL ATIONS.
- 3. ALL BOXES, WHETHER OUTLET, JUNCTION, PULL, OR EQUIPMENT SHALL BE FURNISHED WITH APPROPRIATE COVERS.
- 4. NO SECTIONALIZED BOXES SHALL BE USED.
- 5. ALL EMT CONDUIT FITTINGS SHALL BE COMPRESSION TYPE.
- 6. ALL FIELD CUTS OF GALVANIZED ITEMS SHALL BE BRUSHED WITH MARINE GRADE GALVANIZING.
- 7. ALL METALLIC OBJECTS EXPOSED TO WEATHER SHALL BE GALVANIZED

B. WIRES & CABLE:

- BUILDING WIRE, UNLESS OTHERWISE INDICATED, SHALL BE 600 VOLT, TYPE THWN INSULATION FOR INTERIOR AND EXTERIOR USE. CONDUCTORS SHALL BE SOFT DRAWN COPPER OF NOT LESS THAN 98% CONDUCTIVITY. NO ROMEX OR AC (BX) CABLE WILL BE ALLOWED ON THE PROJECT.
- 2. NO WIRE SMALLER THAN NO. TWELVE (12) AWG SHALL BE USED UNLESS OTHERWISE INDICATED. CONDUCTORS SHALL BE CONTINUOUS FROM OUTLET TO OUTLET AND FROM TERMINAL BOARD TO POINT OF FINAL CONNECTION, AND NO SPLICE SHALL BE MADE EXCEPT WITHIN OUTLET OR JUNCTION BOXES. ALL CONDUCTORS SHALL BE OF THE SIZES AS INDICATED. ALL WIRES NO. EIGHT (8) AWG AND LARGER SHALL BE STRANDED. THE CONTRACTOR SHALL MAKE WIRING CONNECTIONS OF ALL ELECTRICAL EQUIPMENT REQUIRING ELECTRICAL SERVICE. WIRES AND CABLES SHALL BE AS MANUFACTURED BY PIRELLI, ROYAL, AND TRIANGLE OR EQUIVALENT.
- 3. ALL WIRING SHALL BE COLOR CODED. MATCH EXISTING SYSTEM COLOR CODING WHERE APPLICABLE.

C. DISCONNECTS:

FURNISH AND INSTALL SAFETY SWITCHES WHERE INDICATED AND AS REQUIRED FOR MOTOR OUTLETS OR OTHER
EQUIPMENT. SWITCHES SHALL BE OF SIZE, NUMBER OF POLES AND FUSED OR NON-FUSED, AS REQUIRED FOR JOB
CONDITIONS AND THE NATIONAL ELECTRICAL CODE.

D. DISCONNECTS:

- PROVIDE GROUND FRO ALL RACEWAYS, DEVICES, AND UTILIZATION EQUIPMENT PERMANENTLY AND EFFECTIVELY IN ACCORDANCE WITH THE NATIONAL ELECTRICAL CODE, AS HEREINAFTER SPECIFIED. ALL GROUNDING AND BONDING CONNECTIONS SHALL BE SOLDERLESS.
- 2. PROVIDE INSULATED GROUNDING CONDUCTORS FOR FEEDER AND BRANCH CIRCUIT WIRING AS CALLED FOR ON THE PLANS. PROVIDE GROUNDING BLOCKS, TERMINALS ETC., FOR CONNECTION OF GROUND WIRE IN ALL DISTRIBUTION EQUIPMENT.







$\overline{}$			
igsqcup		SUBMITTALS	
REV	DATE	DESCRIPTION	BY
1	05/27/20	CLIENT COMMENTS	DB
			1
			+-
			+-
-			1
(I		1

RELEASED BY DATE

MATTHEW JAMERSON 05/27/21



UNAUTHORIZED ALTERATION OR ADDITIONS TO A PLAN BEARING THE SEAL OF A LICENSED ENGINEER OR LAND SURVEYOR IS A VIOLATION OF LOCAL LAW

OFESSIONAL CERTIFICATION. I HEREBY CERTIFY T ESSE DOCUMENTS WERE PREPARED OR APPROVER. AND THAT I AM A DULY LICENSED PROFESSION. GINEER UNDER THE LAWS OF THE STATE OF VIRC ENSE NO. 0402061949 EXP. 03/12/2022

SITE INFORMATIO

AT&T NEW CRAN BUILD

SITE ADDRESS

CRAN_RWSH_ALEXA_045G 432 SOUTH COLUMBUS STREET ALEXANDRIA, VA 22314

SHEET TITLE


ELECTRICAL NOTES

SHEET NUMBER

E-2


DRAWING NOTES:

- PROPOSED UTILITY COMPANY 200 AMP METER/ 100 AMP DISCONNECT COMBO MOUNTED ON
 UTILITY POLE BELOW RRH CABINET. NEW METER GLOBE PROVIDED AND INSTALLED BY UTILITY
 COMPANY. PROVIDE PHENOLIC NAMEPLATE READING "AT&T WIRELESS".
- EXTEND 2" SCH. 40 PVC CONDUIT FROM NEW ELECTRIC VAULT TO NEW POLE (APPROX. 10' FOR ELECTRIC)
- 3. EXTEND SIX (6) PAIR FIBER FROM PROPOSED OMNI-TAP TO SERVE NOKIA ANTENNA/RADIO UNITS MOUNTED ON UTILITY POLE.
- 4. PROPOSED LOCATION OF REMOTE RADIO HEAD MOUNTED ON EQUIPMENT BRACKET. REFER TO STRUCTURAL FOR DETAILS.
- AT&T WIRELESS PROVIDED AND CONTRACTOR INSTALLED ANTENNA MOUNTED ON TOP OF UTILITY POLE.
- ALL EQUIPMENT / CONDUITS MOUNTED ON POLE SHALL BE PAINT TO MATCH EXISTING POLE
 CONDITIONS. COORDINATE FINAL PAINT COLOR WITH AT&T WIRELESS REPRESENTATIVE IN THE
 FIELD
- EXTEND COAX CABLES FROM BOTTOM OF REMOTE RADIO HEAD TO ANTENNA MOUNTED ON TOP OF UTILITY POLE. COORDINATE FINAL COAX SIZE WITH AT&T REPRESENTATIVE.
- 8. AT&T WIRELESS PROVIDED AND CONTRACTOR INSTALLED UTILITY POLE TOP ANTENNA MOUNT.
- . EXTENDED 6 #12 AWG + #12 GROUND 3/4" GREY PVC CONDUIT FROM PANEL / EACH 15AMP BREAKER (TYP. OF 2) VERTICALLY UP UTILITY POLE TO SERVE EACH NOKIA ANTENNA / RADIO UNIT MOUNTED ON UTILITY POLE (TYP. OF 2). REFER TO PANEL SCHEDULE, SHEET C-5, FAR ADDITIONAL INFORMATION.










UTILITY POLE POWER PLAN E-3 NOT TO SCALE











		SUBMITTALS	
REV	DATE	DESCRIPTION	BY
1	05/27/20	CLIENT COMMENTS	DB

RELEASED BY DATE
MATTHEW JAMERSON 05/27/21



UNAUTHORIZED ALTERATION OR ADDITIONS TO A PL BEARING THE SEAL OF A LICENSED ENGINEER OR LAN SURVEYOR IS A VIOLATION OF LOCAL LAW

PROFESSIONAL CERTIFICATION. I HEREBY CERTIFY TH THESE DOCUMENTS WERE PERPARED OR APPROVED E ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF VIRGIN LICENSE NO. 0402061949 EXP. 03/12/2022

SITE INFORMATION

AT&T NEW CRAN BUILD

SITE ADDRESS


CRAN_RWSH_ALEXA_045G 432 SOUTH COLUMBUS STREET ALEXANDRIA, VA 22314

SHEET TITLE

ELECTRICAL DETAILS

SHEET NUMBER

E-3




DRAWING NOTES:

- 1. PROVIDE 8'-0" (MINIMUM) x 5/8" COPPER CLAD STEEL GROUND ROD.
- BURIED GROUND RING SHALL BE #2 AWG, BARE, TINNED, SOLID COPPER
- EXTEND 1#2 AWG GREEN, INSULATED, STRANDED COPPER GROUND CONDUCTOR FROM BURIED GROUND ROD AND EXTEND VERTICALLY UP UTILITY POLE FOR EQUIPMENT GROUNDING.
- EXTEND 1#6 AWG, INSULATED, STRANDED, COPPER GROUND CONDUCTOR FROM EQUIPMENT FRAME AND BOND TO PROPOSED GROUND CONDUCTOR EXTENDING TO BURIED GROUND ROD.
- EXTEND 1#6 AWG, INSULATED, STRANDED, COPPER GROUND CONDUCTOR FROM POWER SUPPLY UNIT (PSU) AND BOND TO PROPOSED GROUND CONDUCTOR EXTENDING TO BURIED GROUND ROD.
- EXTEND 1#6 AWG, INSULATED, STRANDED, COPPER GROUND CONDUCTOR FROM REMOTE RADIO HEAD AND BOND TO PROPOSED GROUND CONDUCTOR EXTENDING TO BURIED GROUND ROD.
- EXTEND 1#2 AWG GREEN, INSULATED, STRANDED COPPER GROUND CONDUCTOR FROM ENCLOSURE OF PROPOSED LOAD CENTER PANEL AND BOND TO BURIED GROUND ROD. REFER TO SERVICE GROUNDING DETAIL, THIS SHEET.
- EXTEND 1#2 AWG GREEN, INSULATED, STRANDED COPPER GROUND CONDUCTOR FROM ANTENNA MOUNT AND BOND TO TO PROPOSED GROUND CONDUCTOR EXTENDING TO BURIED GROUND ROAD.
- EXTEND 1#6 AWG, GREEN INSULATED, STRANDED COPPER GROUND CONDUCTOR FROM EACH NOKIA ANTENNA/RADIO UNIT AND BOND TO GROUND CONDUCTOR EXTENDING DOWN UTILITY POLE TO GROUND BAR MOUNTED IN ENCLOSURE. (NOT SHOWN FOR CLARITY)

GROUNDING GENERAL NOTES:

- ALL GROUNDING CONNECTIONS BELOW GRADE SHALL BE EXOTHERMIC (CADWELD) TO NEAREST GROUND ROD USING ERICO CADWELD "ONE-SHOT" CONNECTIONS.
- ALL EXTERIOR GROUND CONDUCTORS SHALL BE #2 AWG BARE, TINNED SOLID COPPER, UNLESS NOTED
- ALL GROUND CONNECTIONS ABOVE GROUND SHALL BE TWO-HOLE COPPER COMPRESSION TYPE WITH STANDARD LENGTH BARREL (BURNDY# YA2CL-2TC14EI). SINGLE HOLE LUGS ARE NOT ACCEPTABLE.
- ALL MOUNTING HARDWARE FOR EXTERIOR LOCATIONS SHALL BE GALVANIZED INCLUDING NUTS, BOLTS, FLAT
- ALL EXTERIOR MECHANICAL CONNECTIONS SHALL BE MADE USING OXIDE-INHIBITING JOINT COMPOUND. THE COMPOUND SHALL BE APPLIED TO ALL SURFACES OF BOLTS. WASHERS, NUTS AND CONNECTION SURFACES OF GROUND BAR PLATES. ALL BARE COPPER SURFACES OF CONDUCTORS SHALL BE COATED PRIOR TO LUGGING. JOINT COMPOUND SHALL BE NO-OX.
- ALL EXOTHERMIC WELD CONNECTIONS AND FIELD CUTS OF METALLIC OBJECTS EXPOSED TO WEATHER SHALL BE FIRST SPRAYED WITH COLD GALVANIZING (AFTER COOL DOWN) THEN BE TOPPED WITH BRUSH ON MARIN GRADE GALVANIZING
- ALL CONDUIT USED AS SLEEVES FOR GROUNDING OR BONDING CONDUCTORS SHALL BE PVC.
- ALL GROUND RODS SHALL BE DRIVEN VERTICALLY USING A GROUND ROD SHIELD TO PREVENT THE ENDS FROM "MUSHROOMING"
- THE MAXIMUM RESISTANCE OF THE COMPLETED GROUND SYSTEM SHALL NOT EXCEED 5 OHMS ON ANY PART OF THE SYSTEM. IF DUE TO SOIL CONDITIONS OR OTHER PARAMETERS, THIS MAXIMUM IS EXCEEDED, CONTRACT LYNCOLE FOR XIT GROUNDING DESIGN.
- 10. ALL EXTERIOR GROUND BARS SHALL BE GALVANIZED STEEL, SIZE AS NOTED ON PLANS, AND MANUFACTURED BY ELECTRIC MOTIONS COMPANY, INC. (WWW.ELECTRICMOTIONSCOMPANY.COM).
- 11. JOINT COMPOUND FOR GROUNDING SHALL BE NO-OX.

- GROUND ROD TO BE INSTALLED IN UNDISTURBED EARTH.
 THIS POLE CAN SERVE TWO STREETLIGHT BRACKETS ON OPPOSITE SIDES. SERVE SECOND STREETLIGHT WITH SEPARATE CONDUCTORS IN CHAMBER "C".









$\ $ $igspace$		SUBMITTALS	`
RE\	/ DATE	DESCRIPTION	BY
1	05/27/20	CLIENT COMMENTS	DB
	+		

RELEASED BY 05/27/21 MATTHEW JAMERSON



BEARING THE SEAL OF A LICENSED ENGINEER OR LAN SURVEYOR IS A VIOLATION OF LOCAL LAW

AT&T NEW CRAN BUILD

SITE ADDRESS

CRAN_RWSH_ALEXA_045G **432 SOUTH COLUMBUS** STREET **ALEXANDRIA, VA 22314**

SHEET TITLE

ELECTRICAL DETAILS CONT.

SHEET NUMBER